



LACKAGH EB & WB BUS STOPS
 EASTBOUND STOP NO.: 553431 & WESTBOUND STOP NO.: 553411
 APPROXIMATE COORDINATES: EB STOP 53.370092, -8.891028; WB STOP 53.370053, -8.890827

- BUS SHELTER FOUNDATION & SUPERSTRUCTURE**
1. SHELTER SUPERSTRUCTURE SUPPLIED AND ERECTED BY BAUER MEDIA. THE MAIN CONTRACTOR UNDERTAKES ALL EXCAVATION, FOUNDATION & CONCRETE WORKS, & PROVIDE ASSISTANCE TO BAUER MEDIA AS REQUIRED.
 2. REFER TO WORKS REQUIREMENTS FOR FURTHER INFORMATION.
- SURFACE REINSTATEMENT**
3. ALL OPENING AND REINSTATEMENT OF CARRIAGEWAYS, FOOTWAYS & LANDSCAPED AREAS IN FULL COMPLIANCE WITH "GUIDELINES FOR MANAGING OPENINGS IN PUBLIC ROADS" AKA "THE PURPLE BOOK".
 4. REINSTATEMENT SHALL BE TO STANDARD DRAWINGS NO'S SD1 TO SD 14 OF "THE PURPLE BOOK".
- GENERAL**
5. THE CONTRACTOR IS TO MAKE THEMSELVES FAMILIAR WITH THE SITE AND CONFIRM THE POSITIONING OF INFRASTRUCTURE BEFORE COMMENCING THE WORKS. THE CONTRACTOR IS TO AGREE THE POSITIONING OF INFRASTRUCTURE WITH THE ENGINEER ON SITE PRIOR TO ANY WORKS COMMENCING.
 6. IN THE EVENT OF ANY DOUBT REGARDING ANY ITEM OF DESIGN, SPECIFICATION OR CONSTRUCTION DETAIL, CONSULT THE EMPLOYERS' REPRESENTATIVE OR RESIDENT ENGINEER FOR GUIDANCE.
 7. DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS. CONTRACTOR IS TO CHECK ALL DIMENSIONS ON SITE PRIOR TO COMMENCEMENT OF WORKS. ANY DISCREPANCIES ARE TO BE REFERRED TO THE ENGINEER.
 8. COPYRIGHT: THE DESIGN AND DETAILS SHOWN ON THIS DRAWING ARE APPLICABLE TO THIS PROJECT ONLY AND MAY NOT BE REPRODUCED IN WHOLE OR IN PART OR TO BE USED FOR ANY OTHER PROJECT OR PURPOSE WITHOUT WRITTEN PERMISSION OF GALWAY COUNTY COUNCIL WITH WHOM COPYRIGHT RESIDES.
- CHLORINATED RUBBER YELLOW PAINT**
9. CONCRETE AND OTHER CEMENTITIOUS SURFACES MUST BE CLEAN AND DRY BEFORE APPLICATION OF PAINT PRIMER UNIPRIME X250.
 10. LINE MARKING APPLIED TO PRIMED SURFACE USING VIALINE F210 (TRAFFIC YELLOW COLOUR) BY ROLLER OR AIRLESS SPRAY APPLICATOR.
 11. ANTI-SLIP GLASS GRAIN GEM500 APPLIED IMMEDIATELY AFTER APPLICATION OF LINE MARKING WHILE THE COATING IS STILL WET.

KEY:

	KASSEL KERB (INCLUDES TRANSITION KERBS) - 160mm HIGH BY KILLESHAL CONCRETE OR EQUIV. LAID IN 700mmW x 150mmD HAUNCH OF C16 / 20 CONCRETE.
	PRECAST/IN-SITU KERB (125mm UPSTAND) TYPE A TO CC-SCD-01109
	PRECAST/IN-SITU KERB (TRANSITION KERB)
	PROPOSED GULLY TO TII-CC-SCD00510 & 05144
	REINSTATEMENT OF PAVEMENT TO PURPLE BOOK SD-6
	TYPE 1 CONCRETE FOOTWAY TO TII CC-SCD-01105
	EXISTING BUILDING (FOR INDICATIVE PURPOSES)
	EXISTING BOUNDARY WALL (FOR INDICATIVE PURPOSES)



Comhairle Chontae na Gaillimhe
Galway County Council

GALWAY COUNTY COUNCIL
Roads & Transportation Division

PROJECT:	BUS STOP ENHANCEMENTS	
TITLE:	GENERAL ARRANGEMENT LACKAGH BUS STOPS	
STATUS: TEND	DATE: 06/25	SCALE: 1:150
DRAWN: DG	CHECKED: XX	APPROVE: XX
DWG NO: GCO/25/0005-T2-DWG-011-A	REV: P01	